


**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections



**1. Name**

historic Badin Multiple Resource Nomination

and/or common Badin Historic District, West Badin HD, Narrows Dam and Power Complex

**2. Location**

street & number \_\_\_\_\_ not for publication \_\_\_\_\_

city, town Badin \_\_\_\_\_ vicinity of \_\_\_\_\_ congressional district 8

state North Carolina code 37 county Stanly code 167

**3. Classification**

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input checked="" type="checkbox"/> educational
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input checked="" type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<u>N/A</u>	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input checked="" type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

**4. Owner of Property**

name multiple ownership

street & number \_\_\_\_\_

city, town \_\_\_\_\_ vicinity of \_\_\_\_\_ state \_\_\_\_\_

**5. Location of Legal Description**

courthouse, registry of deeds, etc. Stanly County

street & number \_\_\_\_\_

city, town Albemarle state North Carolina

**6. Representation in Existing Surveys**

title HAER has this property been determined eligible?  yes  no

date 1974  federal  state  county  local

depository for survey records N.C. Division of Archives and History

city, town Raleigh state North Carolina

# 7. Description

<b>Condition</b>		<b>Check one</b>	<b>Check one</b>
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

## Describe the present and original (if known) physical appearance

Badin, North Carolina, in Stanly County is located near the shore of Badin Lake, a body of water formed by the damming of the Narrows of the Yadkin River.

Construction of the residential, institutional and commercial structures in Badin was begun in 1912 by the Southern Aluminum Company of America. In 1926, according to the Sanborn Insurance Company map, the village was comprised of 1,094 structures. In 1981, 527 of these structures remain, along with 157 post 1926 buildings, 567 have been demolished.


A planned community built to serve the workers of the construction crews and the workers of the aluminum reduction plant, Badin was divided into two distinct neighborhoods, one Negro (or "Colored" on the Sanborn map), now called West Badin, and one White. The two sections are divided physically by the Alcoa Plant and Highway 740.

Architectural elements which unify the two separate villages can be seen primarily in the institutional and public buildings, in street signs and landscaping. A unifying element is the handsome, variously patterned brick work in the public buildings, featuring stretchers of warm red brick with dark glazed headers. The street names in both Badin and West Badin are prominently marked by 6 ft. granite columns at each intersection. Alcoa encouraged landscaping efforts and today Badin residents take pride in the thousands of azalea bushes and mature trees which thrive in the villages.

The irregular street plans of the villages follow the gently hilly streets which are canopied by mature deciduous trees. The houses in Badin are well cared for, the yards landscaped. The houses are well-spaced with lots of room for greenery and trees, and from its origin, the town has been known for its gardens. The sidewalks and curbed and guttered streets are immaculate. There is a European flavor in the remaining rock walled open storm drains. Today a walk down the several dirt alleys reveals a profusion of small vegetable gardens, chickens and penned hunting dogs.

It is interesting to note that the street names in the village of Badin are primarily those of trees: Pine, Walnut, Poplar, Hickory, Chestnut, Magnolia, Elm, Maple, Spruce, Cedar, Apple, Cherry, Pear and Holly. In contrast, those of West Badin are named primarily for Civil War heroes and early 20th century political figures, possibly an attempt to inspire patriotic sentiments in the black citizenry. Street names include: Sumpter, Jackson, Grant, Lee, Sherman, Lincoln, Dewey and Roosevelt.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 7

Page 1

Quadrplexes, duplexes, and small bungalows comprise the primary housing stock in Badin, with smaller duplexes and bungalows (and no quadrplexes), comprising the majority of West Badin's housing. Both sections boasted fine school buildings and while West Badin's school is abandoned and vandalized now, the Badin School, with intrusive additions, still functions as an elementary school for the community.

Handsome churches were constructed on both sides of town and continue to have active congregations. In Badin they include the imposing Baptist Church on Falls Road, the Presbyterian Church on Spruce Avenue, and the Methodist Church on Pine Avenue, which began as a frame structure that was later brick veneered, then replaced in 1974 by a new structure.

Original churches in West Badin include the First Baptist Church on Roosevelt Road, and the McDonald's Chapel AME Zion Church on Dewey Street. The original Colored Community Headquarters is now being used as the Second Baptist Church.

Small commercial districts were constructed in both sections of town. Both are now largely abandoned. In West Badin empty store fronts form a bleak entrance into the village, while in Badin, those remaining are in good condition, but unused. Retail traffic is now centered in the nearby town of Albemarle, or in Charlotte, forty miles away.


The former Badin Hospital built by Alcoa, has been adapted to serve as the company's Personnel Department and medical services are now provided in the 500-bed Stanly County Hospital in Albemarle.

Today the two villages remain racially separate: Badin is White, and West Badin is Black. While West Badin contains some fine public buildings, the original housing stock is in need of general maintenance. West Badin also lacks the sidewalks, curbs and gutters of its neighbor.

The predominant styles of residential buildings in Badin can be divided into two major categories: housing built by the French-owned Southern Aluminum Company between 1912 and 1915 and residences constructed by Alcoa between 1915 and 1920. The French company housing, designed by the architectural firm of Goodrich and Pierson of New York, consisted of row house quadrplexes, duplexes, a superintendent's residence on Henderson Street, and a Club House for single male employees and visitors. Alcoa's residential units were designed by the Pittsburgh firm of G. H. Giesey and consist largely of small four and five-room bungalows.<sup>2</sup>

The striking four-apartment quadrplexes "(were) of a design then popular in France (and) were built in an area now served by Boyden Street (named for a mayor of Salisbury, Archibald Henderson Boyden), Kirk Place, Spruce Street, Maple Street, Nantahala Street, Willow Street, Falls Road, Cedar Street and Holly Place."<sup>3</sup>

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 7

Page 2

Originally Alcoa owned, controlled and rented the units, but since the 1930s they are individually owned and great attempts have been made to individualize these row houses. For example, a section of yellow vinyl siding may lie next to asbestos siding, next to the original white clapboard, or next to grey clapboards. Each front and rear yard is differently landscaped with a number of dissimilar plantings. But rather than creating a busy jumble, the effect is rather like a contemporary block of townhouse apartments.


The quadraplexes share many original architectural features with variances occurring primarily in the rooflines. These two-story rectilinear, one bay deep units have a centrally located projecting shed roofed screened porch which provides access to the two central units. Projecting screened or enclosed end porches provide access to the end units. Each apartment has its own centrally located brick chimney. Windows are six-over-six sash and are often paired or grouped in threes. Rooflines vary from the cross gables of the quadraplex at 27-33 Cedar, to the high hipped roof of 36-38 Cedar (originally a quadraplex, now a duplex), to the gable roof of 17-23 Holly Place with a center ridge that runs parallel to the street and whose end gables slope steeply to form the roofline of the projecting end porches. Trim is simple on these clapboard sheathed houses, often only exposed brackets supporting the gable ends.

A large number of the smaller single family bungalows shown on the 1926 Sanborn map are gone, some disassembled and moved outside of town. According to Mr. A. J. Rice, retired Alcoa engineer:

"(Alcoa), as soon as it had acquired the holdings of the Southern Aluminum Company, made a definite effort to furnish housing for its employees, which at the time was necessary because there were then few private automobiles and fewer good roads on which to use them. Several hundred houses were built in the white and Negro parts of town ranging in the white town, from seven room 'bungalows' to three room cottages and in the Negro part of town, from three room to four room cottages. As transportation facilities increased, as construction work dwindled and more efficient labor-saving equipment was developed in the plant, the necessity for housing in Badin became less acute so that in the Depression years of the early 1930s, practically all of the smaller cottages were sold 'as was' to be dismantled and removed from the premises. This opened a large area of the white town which already had water and sewer services, to the building by individuals of better homes on larger lots, laid out and sold to them by the Company."<sup>4</sup>

The house at 15 Holly Place is typical of the approximately 100 single family bungalows which comprise the bulk of the surviving factory housing in the White section of Badin. These bungalows are located primarily along Pine Avenue, Spruce Avenue, Cedar, Willow, and Falls Road. Number 15 Holly Place is one-story, three bays wide, four bays deep, clapboarded, with an engaged front porch with simple porch posts and railings.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 7

Page 3

In many cases, on this bungalow type, the front porch is either screened in or has since been enclosed. The hipped roofs, with exposed rafter ends, are oriented longitudinally in order to make the best use of the narrow lots. Two rather squat interior brick chimneys pierce the roof. Many have small centrally located or recessed and offset back porches. While it is readily apparent that all of the remaining houses are of the same basic design, they have been individually owned for approximately forty years and they are now differentiated in appearance by replacement siding and roof coverings, and by their treatment of the front porch, landscaping and various paint colors.

Perhaps the most architecturally distinctive residences in Badin are located on Henderson Street across from the Badin School. Typical of these are the single family dwellings at 48 and 50 Henderson Street. These 1½ story, five bay wide, double pile, clapboard structures are reminiscent of the French Colonial style with their low pavilion type roofs which feature central shed dormers with four small one-over-one sash windows. Six-over-six windows are paired in the end gables, which are accented by vertical board and batten siding and decorative brackets supporting the overhanging roof. The roof is crowned by an offset interior brick chimney. Paired six-over-six sash windows flank the projecting engaged central screened porch, with a simple railing and balusters, sheltering the recessed main entrance. These dwellings are in excellent condition.

Also notable are the three duplexes on Henderson Street. The two-story symmetrical duplexes are of simple, but pleasing proportions, and contain many of the characteristic elements found in Badin including the projecting engaged screened porches and recessed main entrances. A gabled dormer, featuring paired six-over-six sash windows, projects from each face of the steeply sloping gabled roof. Each has exposed rafter ends and simple supporting brackets. A ribbon of four six-over-six sash windows light the first floor and three six-over-six, the second floor. Each half has an end chimney of brick with a modest corbelled cap.

The Club House (now the Stanly County Country Club) is set amidst a pine grove on a hill commanding a view of the village. It was constructed 1912-1914 by the French Company. The main Club House and an annex (built by Alcoa after 1915) are connected by an open colonnade. Both the Club House and the annex are three-stories, sheathed with white clapboards. Both structures have a profusion of six-over-six sash windows, often paired or in groups of three.

The main Club House is built in a modified U shape with the central portion facing north with east and west wings projecting at 45 degree angles. The graceful one-story wraparound porch, supported by Doric columns is cool and shady. The central block has a trio of bay windows projecting on the second-story elevation. Shed dormers project from the roof of the central block and east and west wings. The entrance consists of a pair of glass doors flanked by sidelights and a transom. Entrance to the east and west wings is also through French doors. Replacement asphalt shingles cover the roof with its central brick chimney. Wooden lattice infills between the brick piers of the low foundation.

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number 7

Page 4

A covered Doric columned arcade topped by a simple balustrade connects the Club House to the three-story annex. Its most prominent features are the identical three-story verandahs at both ends, with their exterior stairs forming strong diagonal lines, reminiscent of resort architecture. The spacious first and second-story porches are surrounded by simple balustrades and are supported by Doric columns. There is a smaller balustraded third-story porch supported by posts. As in so many of the smaller Badin dwellings, the rafter ends are exposed. The annex's many windows are again paired, or in bands of three, but they differ from the commonly found six-over-six sash types. These are more deeply inset and consist of six small panes clustered near the top, with three long panes beneath. The annex retains its original slate roof and rests on a stuccoed foundation.

The remaining original commercial buildings in Badin, largely vacant, but in good condition, are grouped along Falls Road, Walnut and Pine Streets, the most prominent being the "Commercial Block" at the corner of Pine Street and Yadkin Court. This is a large, rectangular handsome structure distinguished by its size, prominent corner site and fine brick work. The red brick with dark glazed headers are laid in Flemish bond with brick pilasters dividing the retail units, cornice corbelling and row of bricks set on end over the groups of three eight-over-eight second-story sash windows. Access to the second floor space is through paired double doors in the base of the tower-like units. These entrances are further marked on the second-story by a large arch-headed opening in the stairwell containing paired fully glazed doors below a fanlight, the doors open onto a small wrought iron balcony.

Echoing many of these elements on a smaller and more modest scale, is the Badin Radio Shop on Falls Road. The two store fronts are divided by a thin bay containing an entrance to the stairs to the second level. The door to the entrance is topped by a fanlight, flanked by brick pilasters, simple corbelled cornice and a row of bricks set on end over the paired one-over-one sash second-story windows.

The commercial structures built along Falls Road are, for the most part, in very good and nearly original condition with few modern signs and no modern facade replacement materials to mask their utilitarian purposes as first floor commercial space and second floor office space. These buildings are still maintained by Alcoa.

It should be noted that Badin once boasted a fine community theatre. This building "which dominated the early Badin landscape" was built by Alcoa in 1917-1918 and dedicated by Governor Thomas Walter Bickett on Memorial Day, 1918.

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number 7

Page 5


An afternoon of speeches and music, culminating in a dance in the spacious 'ballroom' on the second floor of the building. This space was later used for many activities. Two or three lodges originally met there. Frequent community dances were held there and, with the installation of movable netting around the floor, basketball games were played there. The theatre floor was commodious. Together with its large balcony, it would seat about 700 persons. This building was said to be the largest theatre between Richmond and Atlanta when it was built. Periodically, plays were held by local talent and many road shows stopped by for a one night stand. School assemblies were held there. In between and regularly there were 'moving picture' shows.

The use of the theater declined as the automobile gave the population more mobility. Eventually the theatre was abandoned and the Masonic Lodge was the sole tenant. In 1959 the building was torn down; it was replaced on the site by the new Post Office building.

The Badin Hospital, built in 1916-1917 and set back from Falls Road on a large landscaped lot, is a one-story brick (Flemish bond with glazed headers), Y-shaped building resting on a quarried stone foundation. The central portion, one bay deep, serves as a foyer with the two wings extending at angles to the rear from it. A full width pedimented porch has square posts supporting a closed pediment with a circular louvered bull's eye ventilator. The porch balustrade is of characteristically plain, slender, closely spaced balusters. The six bay wings are lighted by six-over-six sash windows, each with flat granite arch centered by a keystone. The end of each wing features a stuccoed pediment accented by white trim with a bull's eye ventilator. A central door flanked by paired windows provides access at the wing ends. The Badin Hospital, adapted for use as Alcoa's Personnel Department, is a handsome building. The grouping of the windows, granite lintels, stuccoed pediments, coursed bases and Flemish bond lend the former Hospital a distinct elegance.

No company town could be complete without the company built churches, and several examples of the sure hand of the Badin masons remain. Perhaps the most imposing structure in Badin is the Badin Baptist Church on Falls Road. An earlier frame building (the Ebenezer Baptist Church) occupied the site and was a well known landmark. The site was later flooded when the dam was built and the new church was built closer to the road. The present large brick church was built in 1918-1919 under the leadership of Rev. Arnett. (Arnett planned to establish a church school there, hence the relatively large class room space. The school was never started). Stylistically the church contains many elements of Roman Classicism, but its basic classical symmetry is somewhat obscured by the eclectic busyness of the brick pattern and use of white painted stucco as accents against the red brick.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 7

Page 6


Built on a raised first floor or podium and approached by a broad, steep flight of stairs, the main facade features a large two-story projecting portico with pediment supported by four fluted Ionic columns. A white painted Greek cross is set in a brick circle in the center of the pediment. Fluted Ionic pilasters bracket the panelled double front doors with stained glass transom, which are flanked by transomed rectangular stained glass windows. Above these are stuccoed rectangles centered by bricks laid to form a diamond. Surmounting these are stained glass hemispherical windows. On either side of the prominent portico are fanciful brick work, two-story rectangular panels with a center circle enclosing a white stucco diamond. At each corner of the panel are diagonal white squares. The church is crowned by an octagonal dome (creating a domed sanctuary). Round ventilators and hooded loud speakers, each outlined by a white rectangle, alternate on each lower panel of the dome. The overall shape of the church reflects the Greek cross and the right and left elevations are identical, with double door side entrances sheltered by smaller classical pedimented porches supported by fluted Ionic columns and pilasters. The multitude of stained glass windows, round rectangular and hemispherical, are accented with white trim.

A more modest example of Badin's classically inspired churches is the Presbyterian Church on Spruce Avenue at Falls Road, a temple form building with three Doric columns supporting the pediment. The rafter ends are exposed along the cornice. The two identically panelled double front doors are separated by the center column. Each doorway is framed by a replacement, broken pediment surround. A small rectangular stained glass window tops each door. The five side bays, marked by flat pilasters, contain stained glass windows with sidelights.

Alcoa constructed schools in both West Badin and Badin which share several design characteristics including the plan: a central section topped by a cupola and symmetrical flanking wings. Both schools were operated for some years by Alcoa, but then the buildings and land were deeded to the County. The West Badin School was abandoned when the County high schools were consolidated and racially integrated in the 1960s. It remains vacant and derelict. The Badin School building with its later additions, is still in use as Badin Elementary School, a part of the Stanly County school system.

The central portion of the one-story brick Badin Elementary School on Henderson Street is hip roofed with an octagonal dome-covered louvered cupola. The projecting entrance contains double glass and flush panel front doors with sidelights. The doors are topped by a leaded tracery glass fanlight, which is in turn outlined by a four course brick arch with keystone. Decorative brick corbelling outlines the entrance cornice. The rooflines of the identical wings echo the pavilion style of the houses across the street. Every fifth course of the brick work is alternating glazed header and stretcher. The ends of each wing have a center panel of herringbone brick. The walls appear to be largely glass, with long ribbons of nine pane windows amply lighting the central and wing sections.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 7

Page 7

## West Badin

In West Badin the bulk of the surviving original housing consists of two types of bungalows and one duplex type.

One bungalow type, typified by 704 Roosevelt Street is one-story, L-shaped, three bays wide, three bays deep, covered with clapboard with an engaged, full facade screened porch. This bungalow and several others in West Badin retain their original dark slate roofs. Windows are six-over-six sash. Trim is plain with simple brackets supporting the overhanging rafter ends. The rafter ends are exposed along the front and rear elevations. Other bungalows of this type are found primarily on Washington and Mayo Streets.

An example of the second bungalow style can be seen in 417 Jackson Street. It is one-story, two bays wide, two bays deep, with shallow gable front roof and central chimney. Rafter ends are exposed along the side elevations with the gable end centered by a bracket. The structure's most prominent feature is an offset, projecting, fully screened porch which shelters the main entrance. Its roofline echoes that of the main roof, with exposed rafter ends and central bracket. A variation of this type can be seen on Grant Street with a nearly full width screened porch with the entry stairs at the side.

The structure at 228-226 Lincoln Avenue is representative of the duplexes. It is one-story four bays wide, two bays deep, with slate covered gable front roof, central brick chimney, clapboard siding, high brick foundation, exposed rafter ends with brackets. The porch is nearly full facade, hip roofed, with exposed rafter ends. Seventeen additional duplexes of this type are found on Roosevelt and Wayne Streets.

The small cluster of original one-story brick commercial buildings in West Badin have been altered and now stand vacant and vandalized. They do show some fine masonry work which is evident in both Badin and West Badin, with the use of distinctive dark glazed headers.

In West Badin surviving institutional structures built by Alcoa include churches and the Badin Colored School. Prominent among these are the Baptist Church on Roosevelt Road and McDonald's Chapel AME Zion Church on Dewey Street, both Gothic style elements.

The Baptist Church with its steeply pitched, slate covered roof, is of brick, laid in 1-6 common bond with dark glazed headers. Asymmetrical in plan, the one-story church's main feature is an offset square corner tower with flat roof and stucco and brick frieze band. The tower is ventilated by tall thin louvered openings with rounded arches. The main double door entrance is set in a lancet arch with keystone; a quatrefoil is set in the doors' fanlight. A large lancet arch window with heavy muntins and frosted glass dominates the main facade. Smaller windows mark the four bay depth.

**United States Department of the Interior**  
**Heritage Conservation and Recreation Service**

**National Register of Historic Places**  
**Inventory—Nomination Form**



Continuation sheet

Item number 7

Page 8

McDonald's Chapel AME Zion Church is also built on the Gothic theme with somewhat classical variations. Its central projecting tower set in the front facing gable end and bracketed with discordant classical returns, is topped with corbelled crenelations. The main entrance's double doors now replaced with the present glass and aluminum doors is set in a lancet arch with stained glass transom. The belfry is ventilated by paired lancet arch louvered openings and is flanked at the first-story level by stained glass Gothic windows which are repeated in the five bay deep building. One interior and one exterior chimney extend high over the moderately pitched gable roof.

The Badin Colored School (West Badin) has a two-story central block marked by a granite string course, a hipped roof topped by a handsome Greek lantern. One-story hipped roof wings project from the sides of the two-story block, the double front door with fanlight rests under a classical pediment. Trim is simple with boxed eaves and white reveals around the six-over-six sash symmetrically placed windows. Two pairs of simple tall brick interior chimneys extend above the roof of the central portion. When the school was dedicated in 1925, it was "topped with an aluminum-shingled roof that was the first of its kind ever assembled in North Carolina." 6

Narrows Dam and Power Plant

At the time of its completion in the summer of 1917, the Narrows Dam was the world's highest overflow type dam. It was designed by James W. Rickey, chief hydraulic engineer of the Aluminum Company of America. Rickey was a native of Ohio, trained as an engineer at Rensselaer Polytechnic Institute in Troy, New York. Before working for Alcoa, Rickey served the Northern Pacific Railroad and two power companies in Minnesota.<sup>7</sup> The concrete dam he designed at the Narrows of the Yadkin River is 216 feet high and 1654 feet long. The dam creates a head of 177 feet, a reservoir of over 5300 acres, and a shoreline of 115 miles. Badin Lake, created by the dam, is a popular recreational center in the southern Piedmont. The Narrows power plant is a handsome one-story building nine bays wide with a gable roof and six-foot raised monitor. The building stands 160 feet in length and 60 feet wide, 80 feet high on the riverside and 40 feet high on the gateside. The frame and roof-truss system of the plant is steel with a concrete floor and brick and concrete walls. The brick walls, terra cotta tile roof, and large arched windows gives the building a Spanish Revival appearance. Three steel penstocks convey water to the turbine engines that provide power for five generators with an overall capacity of 96,5000 kilowatts. Alcoa generates alternating current through small aluminum cables to rectifiers near the potrooms at the Badin Works, one and one-half miles west of the power plant, where it is converted to direct current for use in the pots. A steel railway and pedestrian triple span Warren lattice truss bridge connects traffic from the west side of the river to the power plant. Also visible at this site are the remains of the French construction projects.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

Continuation sheet

Item number 7

Page 9

Survey Methodology

The base point used in surveying the historic/architectural resources of Badin was the Sanborn insurance company map of 1926 (the only one in existence for Badin). Produced approximately 50 years prior to the survey, the map was used for purposes of comparison with the existing structures. Oral history was also a major source of information, as was a 1977 volume entitled "Recollections of Early Badin," by A. J. Rice, an Alcoa engineer who arrived in the community in 1917. From these sources, it was apparent that there had been little new construction in Badin since 1926.


The findings of the survey were broken down into the following categories: commercial, institutional, and residential--both single and multi-family. The three areas nominated are distinct geographically, as well as in character. There are no natural links between the town and the Narrows Complex, which remains virtually unaltered. The West Badin Historic District, erected by Alcoa for its black employees, and the Badin Historic District, constructed for white workers by the Southern Aluminum Company of America, are separated by Highway 740 and the Alcoa Plant. Structures located between the Badin Historic District and the Badin Lake were built in the 1950s, and the industrial complex was extensively altered and modernized in the 1960s. Therefore, these buildings were not included in the nomination.

Definition of Assessment Categories

- P - Pivotal Those properties which, because of their historical, architectural and/or cultural characteristics, play a primary, central or "pivotal" role in establishing the qualities for which the district is significant.
- C - Contributing Those properties which, while not pivotal, are supportive of, and contribute to, the historical, architectural, cultural and/or archeological characteristics for which the district is significant.
- F - Fill Those properties of later construction, but of similar use, character and materials, which have neither an especially positive nor an especially negative impact on the general characteristics of the district.
- I - Intrusion Those properties, clearly different in use, scale or materials, which have a definite negative impact on the historical, architectural, cultural and/or archeological characteristics for which the district is significant.

100-4-200 (11-79)  
United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page

MAP SUMMARY

Narrows Complex

- 2 pivotal structures
- 1 pivotal historic archaeological site
- 1 contributing structure

Badin Historic District

- 19 pivotal structures
- 181 contributing structures
- 8 contributing archaeological sites (historic period)
- 25 fill properties
- 7 intrusions

West Badin Historic District

- 5 pivotal structures
- 148 contributing structures
- 4 contributing archaeological sites (historic period)
- 49 fill properties
- 4 intrusions

Key to Map

Pivotal--red

Contributing--blue (structures)


Contributing--purple (archaeological site)

Fill--pink

Intrusion--brown

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page


Introduction to Inventory

The following inventory is keyed to the map accompanying the nomination of the Badin Multiple Resource area to the National Register of Historic Places. Each entry is identified according to the significance of the property within the architectural and historic perspective of the Badin community (P for pivotal; C for contributing; F for fill or non-contributing; and I for intrusion). Unless otherwise indicated, all structures and sites dated before 1915 were constructed by the Southern Aluminum Company and designed by the firm of Pierson and Goodrich. All structures dated between 1915 and 1926 were built by the Aluminum Company of America (Alcoa) and designed by the firm of G. H. Giesey. Structures built after 1926 were constructed by private individuals or firms. All structures in the inventory are frame dwellings for workers and supervisors at the Badin Works unless noted otherwise.

Certain structures in the inventory list are described as a specific type such as "Type A" bungalow. These classifications refer to plans developed by Alcoa during the construction of Badin's residential sections. These plans were discovered in the files of the Stanly County Historic Properties Commission and are reproduced as an appendix to the inventory. Only when a structure clearly reflects the original plan has a descriptive type been assigned.

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page

INVENTORY LIST

Narrows Complex


- 1-(P)-Narrows Dam, concrete arch dam, 1917
- 2-(P)-Power House, 1917
- 3-(C)-Truss Bridge, Warren lattice truss, 1917
- 4-(P)-Smelter and Power House Foundations, remains of French Aluminum plant, 1912-14

Badin Historic District

- 5-(C)-Baseball Park, ballfield and grandstand, c. 1920
- 6-(F)-2 Nantahala Street, one-story frame dwelling, post 1926
- 7-(F)-4 Nantahala Street, one-story frame dwelling, post 1926
- 8-(F)-6 Nantahala Street, two-story frame dwelling, post 1926
- 9-(C)-8 Nantahala Street, two-story frame dwelling, c. 1920
- 10-(C)-10 Nantahala Street, one-story frame dwelling, c. 1920
- 11-(F)-12 Nantahala Street, one-story brick dwelling, post 1926
- 12-(C)-2 Tallassee Street, 1½-story frame dwelling, Type A style, 1916-17
- 13-(C)-4 Tallassee Street, 1½-story frame dwelling, Type A style, 1916-17
- 14-(C)-6 Tallassee Street, 1½-story frame dwelling, Type A style, 1916-17
- 15-(C)-8 Tallassee Street, 1½-story frame dwelling, Type A style, 1916-17
- 16-(C)-10 Tallassee Street, 1½-story frame dwelling, Type A style, 1916-17
- 17-(C)-12 Tallassee Street, one-story frame dwelling, c. 1920
- 18-(C)-14 Tallassee Street, one-story frame dwelling, c. 1920
- 19-(F)-16 Tallassee Street, two-story brick dwelling, post 1926
- 20-(C)-18 Tallassee Street, one-story frame dwelling, c. 1920
- 21-(C)-20 Tallassee Street, one-story frame dwelling, c. 1920
- 22-(F)-1 Tallassee Street, one-story frame dwelling, post 1926

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 
- 23-(C)-3 Tallassee Street, one-story frame dwelling, c. 1920, altered
- 24-(F)-7 Tallassee Street, one-story frame dwelling, post 1926
- 25-(C)-9 Tallassee Street, one-story brick dwelling, post 1926
- 26-(C)-11 Tallassee Street, one-story frame dwelling, c. 1920
- 27-(C)-13 Tallassee Street, one-story frame dwelling, c. 1920
- 28-(C)-15 Tallassee Street, one-story frame dwelling, c. 1920
- 29-(F)-17 Tallassee Street, two-story brick dwelling, post-1926
- 30-(C)-19 Tallassee Street, one-story frame dwelling, c. 1920
- 31-(C)-21 Tallassee Street, one-story frame dwelling, c. 1920
- 32-(P)- Badin Hospital, c. 1920 (now Alcoa Personnel Department)
- 33-(F)-21 Henderson Street, two-story brick dwelling, post 1926
- 34-(C)-23 Henderson Street, Type A one-story frame dwelling, 1916-17
- 35-(P)- Henderson Street, Bakin Elementary School, 20-room school with post WWII additions, c. 1920
- 36-(P)-22 Henderson Street, one-story frame dwelling, c. 1916-17
- 37-(P)-24 Henderson Street, one-story frame dwelling, c. 1916-17
- 38-(P)-28-30 Henderson Street, two-story frame duplex, Type "C.A.", 1914
- 39-(P)-32 Henderson Street, one-story frame dwelling, 1916-17
- 40-(P)-36-38 Henderson Street, two-story frame duplex, Type C.A., 1914
- 41-(P)-40 Henderson Street, one-story frame dwelling, 1916-17
- 42-(P)-44-46 Henderson Street, two-story frame duplex, Type C.A., 1914
- 43-(P)-48 Henderson Street, one-story frame dwelling, 1916-17
- 44-(P)-50 Henderson Street, one-story frame dwelling, 1916-17

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form




Continuation sheet	Item number	Page
	45-(P)-52 Henderson Street, one-story dwelling, 1916-17, altered	
	46-(C)-76 Henderson Street, one-story frame dwelling, c. 1920	
	47-(C)-78 Henderson Street, one-story frame dwelling, c. 1920	
	48-(F)-21 Boyden Street, one-story frame dwelling, post 1926	
	49-(F)-23 Boyden Street, one-story frame dwelling, post 1926	
	50-(P)-27-33 Boyden Street, quadraplex, Type B.A., 1913-14, four four-room dwellings	
	51-(P)-35-41 Boyden Street, frame quadraplex, Type B.C., 1913-14, 4 six-room dwellings	
	52-(C)-43-49 Boyden Street, fram quadraplex, Type B.A., 1913-14	
	53-(C)-53 Boyden Street, two-story frame dwelling, c. 1920	
	54-(C)-51 Boyden Street, post 1926 frame dwelling	
	55-(C)-84-90 Nantahala Street, frame quadraplex, 1913-14, Type B.A.	
	56-(C)-91-97 Nantahala Street, frame quadraplex, Type B.A., 1913-14	
	57-(C)-83-87 Nantahala Street, frame quadraplex, Type B.A., 1913-14	
	58-(C)-88-94 Maple Street, frame quadraplex, Type B.A., 1913-14	
	59-(C)-78-84 Maple Street, frame quadraplex, Type B.A., 1913-14	
	60-(P)-63-69 Falls Road, Type B.A. frame quadraplex, 1913-14	
	61-(C)-site of 53-59 Falls Road, quadraplex	
	62-(I)- U.S. Post Office, c. 1960, site of Badin Theater	
	63-(C)-77 Maple Avenue, two-story frame dwelling, c. 1920	
	64-(C)-79-85 Maple Avenue, frame quadraplex, Type B.A., 1913-14	
	65-(C)-89-95 Maple Avenue, quadraplex, Type B.A., 1913-14	
	66-(C)-103-109 Maple Avenue, quadraplex, Type B.A., 1914	
	67-(C)-135-41 Maple Avenue, quadraplex, Type B.A., 1914	
	68-(C)-143-49 Maple Avenue, quadraplex, Type B.A., 1914	

*Correction:*  
2 story w/ partially finished  
3rd story per present  
owner 1-31-01.

**United States Department of the Interior  
Heritage Conservation and Recreation Service**


**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet	Item number	Page
	69-(C)-28-34 Kirk Place, quadraplex, 1913-14	
	70-(C)-38-44 Kirk Place, quadraplex, 1913-14	
	71-(C)-138-144 Maple Avenue, quadraplex, 1913-14	
	72-(C)-128-134 Maple Avenue, Type B.A. quadraplex, 1913-14	
	73-(P)- Badin Club House, c. 1914, (now Stanly County Country Club)	
	74-(P)- Club House Annex, c. 1920	
	75-(C)-84-90 Spruce Street, quadraplex, c. 1914	
	76-(C)-92-98 Spruce Street, quadraplex, c. 1914	
	77-(C)-106-112 Spruce Street, quadraplex, 1914	
	78-(F)-116 Spruce Street, two-story dwelling, once part of 1914 quadraplex	
	79-(F)-120 Spruce Street, two-story dwelling, once part of 1914 quadraplex	
	80-(C)-126-32 Spruce Street, quadraplex, c. 1914	
	81-(C)- site of 136-42 Spruce Street, quadraplex	
	82-(C)-77-79 Spruce Steet, duplex, c. 1914	
	83-(C)-83-89 Spruce Street, quadraplex, c. 1914	
	84-(C)-125-127 Spruce Street, duplex, c. 1914	
	85-(C)-131-135 Spruce Street, triplex, c. 1914	
	86-(C)-141-147 Spruce Street, quadraplex, c. 1914	
	87-(I)- Spruce Street Badin Presbyterian Church, c. 1956, two-story brick structure and one-story brick fellowship hall	
	88-(C)-79-85 Falls Road, quadraplex, c. 1914	
	89-(C)-87-93 Falls Road, quadraplex, c. 1914	
	90-(C)-101-Falls Road, one-story bungalow, c. 1916	

1101-6-300 (11-79)  
United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 
- 91-(C)-103 Falls Road, one-story bungalow, c. 1916  
92-(C)-105 Falls Road, one-story bungalow, c. 1916  
93-(C)-107 Falls Road, one-story bungalow, c. 1916  
94-(C)-109 Falls Road, one-story bungalow, c. 1916  
95-(C)-111 Falls Road, one-story bungalow, c. 1916  
96-(C)-113 Falls Road, one-story bungalow, c. 1916  
97-(C)-115 Falls Road, one-story bungalow, c. 1916  
98-(C)-119 Falls Road, one-story bungalow, c. 1916  
99-(C)-119 Falls Road, one-story bungalow, c. 1916  
100-(C)-121 Falls Road, one-story bungalow, c. 1916  
101-(C)-123 Falls Road, one-story bungalow, c. 1916  
102-(C)-122 Falls Road, one-story bungalow, c. 1916  
103-(C)-120 Falls Road, one-story bungalow, c. 1916  
104-(C)-118 Falls Road, one-story bungalow, c. 1916  
105-(C)-116 Falls Road, one-story bungalow, c. 1916  
106-(C)-114 Falls Road, one-story bungalow, c. 1916  
107-(C)-112 Falls Road, one-story bungalow, c. 1916  
108-(C)-110 Falls Road, one-story bungalow, c. 1916  
109-(C)-108 Falls Road, one-story bungalow, c. 1916  
110-(C)-106 Falls Road, one-story bungalow, c. 1916  
111-(C)-104 Falls Road, one-story bungalow, c. 1916  
112-(C)-102 Falls Road, one-story bungalow, c. 1916  
113-(F)-100 Falls Road, one-story brick dwelling, post 1926  
114-(C)-90-96 Falls Road, quadraplex, c. 1914

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 115-(C)-80-86 Falls Road, quadraplex, c. 1914
- 116-(C)-55-61 Maple Ave., quadraplex, Type B.A., 1914
- 117-(C)-51 Maple Avenue, one-story frame cottage, c. 1915
- 118-(C)-64-68 Falls Road, quadraplex, c. 1914
- 119-(C)-72 Falls Road, one-story brick commerical building, c. 1925
- 120-(C)- Falls Road Park
- 121-(I)-522 Falls Road, brick commercial building, post 1926
- 122-(C)-518-520 Falls Road, two-story brick commercial building, vacant, c. 1920
- 123-(C)-517 Falls Road, one-story brick commercial building, vacant, c. 1920
- 124-(C)-512-515 Falls Road, two-story brick commercial building, c. 1920
- 125-(P)-509 Falls Road, Badin Baptist Church, c. 1925
- 126-(F)-505 Falls Road, Service Station, c. 1935
- 127-(C)-503 Falls Road, two-story commercial building, vacant, c. 1920
- 128-(I)-501 Falls Road, one-story convenience store, post 1926
- 129-(C)-307-308 Walnut Street, two-story brick commercial building, c. 1920
- 130-(C)-510-512 site of Pine Avenue, two-story commercial building, c. 1920-
- 131-(I)-514 Pine Avenue, Union Building, c. 1950
- 132-(C)-520-521 Pine Avenue, one-story brick commercial building, vacant
- 133-(I)-523 Pine Avenue, post-1926 commercial building
- 134-(I)-525 Pine Avenue, Methodist Church, post 1926
- 135-(C)-100 Pine Avenue, one-story bungalow, c. 1920
- 136-(C)-102 Pine Avenue, one-story bungalow, c. 1920
- 137-(C)-104 Pine Avenue, one-story bungalow, c. 1920
- 138-(C)-106 Pine Avenue, one-story bungalow, c. 1920
- 139-(C)-108 Pine Avenue, one-story bungalow, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 140-(C)-110 Pine Avenue, one-story bungalow, c. 1920
- 141-(C)-112 Pine Avenue, one-story bungalow, c. 1920
- 142-(C)-114 Pine Avenue, one-story bungalow, c. 1920
- 143-(C)-116 Pine Avenue, one-story bungalow, c. 1920
- 144-(C)-118 Pine Avenue, one-story bungalow, c. 1920
- 145-(C)-120 Pine Avenue, one-story bungalow, c. 1920
- 146-(C)-122 Pine Avenue, one-story bungalow, c. 1920
- 147-(C)-124 Pine Avenue, one-story bungalow, c. 1920
- 148-(C)-126 Pine Avenue, one-story bungalow, c. 1920
- 149-(C)-128 Pine Avenue, one-story bungalow, c. 1920
- 150-(I)-130 Pine Avenue, one-story brick dwelling, post 1926
- 151-(P)-555-562 Pine Avenue, two-story brick commercial block, partially vacant, c. 1920
- 152-(C)-113 Pine Avenue, one-story bungalow, c. 1920
- 153-(C)-115 Pine Avenue, one-story bungalow, c. 1920
- 154-(C)-117 Pine Avenue, one-story bungalow, c. 1920
- 155-(C)-119 Pine Avenue, one-story bungalow, c. 1920
- 156-(C)-121 Pine Avenue, one-story bungalow, c. 1920
- 157-(C)-123 Pine Avenue, one-story bungalow, c. 1920
- 158-(C)-137 Pine Avenue, one-story bungalow, c. 1920
- 159-(C)-139 Pine Avenue, one-story bungalow, c. 1920
- 160-(C)-143 Pine Avenue, one-story bungalow, c. 1920
- 161-(C)-145 Pine Avenue, one-story bungalow, c. 1920
- 162-(C)-147 Pine Avenue, one-story bungalow, c. 1920
- 163-(C)-149 Pine Avenue, one-story bungalow, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 164-(C)-151 Pine Avenue, one-story bungalow, c. 1920
- 165-(C)-153 Pine Avenue, one-story bungalow, c. 1920
- 166-(F)-155 Pine Avenue, one-story frame dwelling, post 1926
- 167-(C)-212 Spruce Street, one-story bungalow, c. 1920
- 168-(C)-214 Spruce Street, one-story bungalow, c. 1920
- 169-(C)-216 Spruce Street, one-story bungalow, c. 1920
- 170-(C)-218 Spruce Street, one-story bungalow, c. 1920
- 171-(C)-site of 202-208 Spruce quadruplex, c. 1914
- 172-(C)-217 Spruce Street, one-story bungalow, c. 1920
- 173-(C)-209 Spruce Street, one-story brick residence, post 1926
- 174-(C)-211 Spruce Street, one-story bungalow, c. 1920
- 175-(C)-213 Spruce Street, one-story bungalow, c. 1920
- 176-(C)-215 Spruce Street, one-story bungalow, c. 1920
- 177-(C)-217 Spruce Street, one-story bungalow, c. 1920
- 178-(C)-219 Spruce Street, one-story bungalow, c. 1920
- 179-(C)-4 Cherry Street, one-story bungalow, c. 1920
- 180-(C)-6 Cherry Street, one-story bungalow, c. 1920
- 181-(C)-8 Cherry Street, one-story bungalow, c. 1920
- 182-(C)-10 Cherry Street, one-story bungalow, c. 1920
- 183-(C)-14 Cherry Street, one-story bungalow, c. 1920
- 184-(C)-16 Cherry Street, one-story bungalow, c. 1920
- 185-(C)-18 Cherry Street, one-story bungalow, c. 1920
- 186-(C)-20 Cherry Street, one-story bungalow, c. 1920
- 187-(F)- Cherry Street, one-story brick dwelling, post 1926
- 188-(C)-site of eighteen one-story bungalows, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 189-(C)-site of nine one-story bungalows, c. 1920
- 190-(C)-15 Holly Place, one-story four-room cottage, c. 1920
- 191-(F)-17 Holly Place, two-story frame dwelling (once part of quadraplex), c. 1914
- 192-(F)-21 Holly Place, two-story frame dwelling (once part of quadraplex), c. 1914
- 193-(C)-27-33 Cedar Avenue, quadraplex, c. 1914
- 194-(C)-36-38 Cedar Avenue, duplex (once par of quadraplex), c. 1914
- 195-(C)-53 Cedar Avenue, one-story bungalow, c. 1920
- 196-(C)-55 Cedar Avenue, one-story bungalow, c. 1920
- 197-(C)-57 Cedar Avenue, one-story bungalow, c. 1920
- 198-(C)-59 Cedar Avenue, one-story bungalow, c. 1920
- 199-(C)-61 Cedar Avenue, one-story bungalow, c. 1920
- 200-(C)-63 Cedar Avenue, one-story bungalow, c. 1920
- 201-(F)-71 Cedar Avenue, one-story brick dwelling, post 1926
- 202-(F)-50 Cedar Avenue, one-story brick ranch, post 1926
- 203-(C)-56 Cedar Avenue, one-story bungalow, c. 1920
- 204-(C)-58 Cedar Avenue, one-story bungalow, c. 1920
- 205-(C)-60 Cedar Avenue, one-story bungalow, c. 1920
- 206-(C)-62 Cedar Avenue, one-story bungalow, c. 1920
- 207-(C)-64 Cedar Avenue, one-story bungalow, c. 1920
- 208-(C)-66 Cedar Avenue, one-story bungalow, c. 1920
- 209-(C)-68 Cedar Avenue, one-story bungalow, c. 1920
- 210-(C)-70 Cedar Avenue, one-story bungalow, c. 1920
- 211-(C)- site of two, two-story quadraplexes, c. 1915
- 212-(F)-194 Spruce Street, one-story brick dwelling, post 1926

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 213-(F)-196 Spruce Street, one-story brick dwelling, post 1926
- 214-(C)-182-188 Spruce Street, quadraplex, 1915
- 215-(C)-site of three, one-story bungalows and one quadraplex, c. 1915
- 216-(C)-27-33 Willow Street, quadraplex, c. 1915
- 217-(C)-37-43 Willow Street, quadraplex, c. 1914
- 218-(C)-36-42 Willow Street, quadraplex, c. 1915
- 219-(F)- Willow Street, one-story brick dwelling, post 1926
- 220-(C)-53 Willow Street, one-story cottage, c. 1920
- 221-(C)-55 Willow Street, one-story cottage, c. 1920
- 222-(C)-57 Willow Street, one-story cottage, c. 1920
- 223-(C)-59 Willow Street, one-story cottage, c. 1920
- 224-(C)-61 Willow Street, one-story cottage, c. 1920
- 225-(C)-63 Willow Street, one-story cottage, c. 1920
- 226-(C)-65 Willow Street, one-story cottage, c. 1920
- 227-(C)-67 Willow Street, one-story cottage, c. 1920
- 228-(C)-69 Willow Street, one-story cottage, c. 1920
- 229-(F)-71 Willow Street, one-story frame dwelling, post 1926
- 230-(C)-54 Willow Street, one-story cottage, c. 1920
- 231-(C)-56 Willow Street, one-story cottage, c. 1920
- 232-(C)-58 Willow Street, one-story cottage, c. 1920
- 233-(C)-60 Willow Street, one-story cottage, c. 1920
- 234-(C)-62 Willow Street, one-story cottage, c. 1920
- 235-(C)-64 Willow Street, one-story cottage, c. 1920
- 236-(C)-66 Willow Street, one-story cottage, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page


- 237-(C)-68 Willow Street, one-story cottage, c. 1920  
238-(C)-70 Willow Street, one-story cottage, c. 1920  
239-(C)-162-68 Spruce Street, quadraplex, c. 1915  
240-(C)-154-160 Spruce Street, quadraplex, c. 1915  
241-(C)-29-35 Maple Avenue, quadraplex, c. 1915  
242-(C)-39-45 Maple Avenue, quadraplex, c. 1915  
243-(C)-62-68 Maple Avenue, quadraplex, c. 1915  
244-(C)-site of Community House, Maple Avenue, c. 1916

West Badin Historic District

- 245-(C)-400 Lee Street, one-story cottage, c. 1920  
246-(C)-402 Lee Street, one-story cottage, c. 1920  
247-(C)-site of thirteen cottages, c. 1920  
248-(C)-401 Grant Street, one-story cottage, c. 1920  
249-(C)-403 Grant Street, one-story cottage, c. 1920  
250-(C)-405 Grant Street, one-story frame cottage, c. 1920  
251-(C)-407 Grant Street, one-story cottage, c. 1920  
252-(C)-409 Grant Street, one-story cottage, c. 1920  
253-(C)-411 Grant Street, one-story cottage, c. 1920  
254-(C)-415 Grant Street, one-story cottage, c. 1920  
255-(C)-502 Grant Street, one-story cottage, c. 1920  
256-(C)-506 Grant Street, one-story cottage, c. 1920  
257-(C)-510 Grant Street, one-story cottage, c. 1920  
258-(C)-514 Grant Street, one-story cottage, c. 1920  
259-(C)-518 Grant Street, one-story cottage, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 213-(F)-196 Spruce Street, one-story brick dwelling, post 1926
- 214-(C)-182-188 Spruce Street, quadraplex, 1915
- 215-(C)-site of three, one-story bungalows and one quadraplex, c. 1915
- 216-(C)-27-33 Willow Street, quadraplex, c. 1915
- 217-(C)-37-43 Willow Street, quadraplex, c. 1914
- 218-(C)-36-42 Willow Street, quadraplex, c. 1915
- 219-(F)- Willow Street, one-story brick dwelling, post 1926
- 220-(C)-53 Willow Street, one-story cottage, c. 1920
- 221-(C)-55 Willow Street, one-story cottage, c. 1920
- 222-(C)-57 Willow Street, one-story cottage, c. 1920
- 223-(C)-59 Willow Street, one-story cottage, c. 1920
- 224-(C)-61 Willow Street, one-story cottage, c. 1920
- 225-(C)-63 Willow Street, one-story cottage, c. 1920
- 226-(C)-65 Willow Street, one-story cottage, c. 1920
- 227-(C)-67 Willow Street, one-story cottage, c. 1920
- 228-(C)-69 Willow Street, one-story cottage, c. 1920
- 229-(F)-71 Willow Street, one-story frame dwelling, post 1926
- 230-(C)-54 Willow Street, one-story cottage, c. 1920
- 231-(C)-56 Willow Street, one-story cottage, c. 1920
- 232-(C)-58 Willow Street, one-story cottage, c. 1920
- 233-(C)-60 Willow Street, one-story cottage, c. 1920
- 234-(C)-62 Willow Street, one-story cottage, c. 1920
- 235-(C)-64 Willow Street, one-story cottage, c. 1920
- 236-(C)-66 Willow Street, one-story cottage, c. 1920

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 260-(C)-523 Jackson Street, one-story cottage, c. 1920
- 261-(C)-515 Jackson Street, one-story cottage, c. 1920
- 262-(C)-511 Jackson Street, one-story cottage, c. 1920
- 263-(C)-507 Jackson Street, one-story cottage, c. 1920
- 264-(C)-503 Jackson Street, one-story cottage, c. 1920
- 265-(F)-420 Grant Street, one-story brick dwelling, post 1926
- 266-(C)-416 Grant Street, one-story cottage, c. 1920
- 267-(F)-412 Grant Street, one-story frame dwelling, post 1926
- 268-(C)-408 Grant Street, one-story cottage, c. 1920
- 269-(C)-406 Grant Street, one-story cottage, c. 1920
- 270-(C)-402 Grant Street, one-story cottage, c. 1920
- 271-(C)-407 Jackson Street, one-story cottage, c. 1920
- 272-(C)-409 Jackson Street, one-story cottage, c. 1920
- 273-(C)-415 Jackson Street, one-story cottage, c. 1920
- 274-(C)-417 Jackson Street, one-story cottage, c. 1920
- 275-(C)-419 Jackson Street, one-story cottage, c. 1920
- 276-(C)-421 Jackson Street, one-story cottage, c. 1920
- 277-(C)-423 Jackson Street, one-story cottage, c. 1920
- 278-(C)-503 Sherman Street, one-story cottage, c. 1920
- 279-(C)-507 Sherman Street, one-story cottage, c. 1920
- 280-(C)-509 Sherman Street, one-story cottage, c. 1920
- 281-(C)-601 Sherman Street, one-story cottage, c. 1920
- 282-(C)-605 Sherman Street, one-story cottage, c. 1920
- 283-(F)-607 Sherman Street, one-story cottage, post 1926

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 284-(F)-701 Sherman Street, one-story cottage, post 1926
- 285-(I)-705 Sherman Street, trailer
- 286-(F)-709 Sherman Street, one-story frame dwelling, post 1926
- 287-(F)-320 Washington Street, one-story frame dwelling, post 1926
- 288-(F)-316 Washington Street, one-story frame dwelling, post 1926
- 289-(F)-312 Washington Street, one-story frame dwelling, post 1926
- 290-(C)-306 Washington Street, one-story cottage, c. 1920
- 291-(C)-304 Washington Street, one-story cottage, c. 1920
- 292-(C)-302 Washington Street, one-story cottage, c. 1920
- 293-(F)-303 Washington Street, one-story frame dwelling, post 1926
- 294-(C)-307 Washington Street, one-story cottage, c. 1920
- 295-(C)-309 Washington Street, one-story cottage, c. 1920
- 296-(C)-313 Washington Street, one-story cottage, c. 1920
- 297-(C)-315 Washington Street, one-story cottage, c. 1920
- 298-(C)-317 Washington Street, one-story cottage, c. 1920
- 299-(C)-319 Washington Street, one-story cottage, c. 1920
- 300-(F)-323 Washington Street, one-story frame dwelling, post 1926
- 326 301-(F)-320 Sumpter Street, one-story frame dwelling, post 1926
- 302-(C)-324 Sumpter Street, one-story cottage, c. 1920
- 303-(C)-322 Sumpter Street, one-story cottage, c. 1920
- 304-(C)-320 Sumpter Street, one-story cottage, c. 1920
- 305-(C)-318 Sumpter Street, one-story cottage, c. 1920
- 306-(C)-316 Sumpter Street, one-story cottage, c. 1920
- 307-(C)-314 Sumpter Street, one-story cottage, c. 1920

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 308-(C)- Sumpter Street, site of three bungalows, c. 1920
- 309-(F)-320 Sumpter Street, one-story frame dwelling, post 1926
- 310-(C)-565-569 Roosevelt Road, one-story brick commercial building, divided into five businesses, c. 1920
- 311-(F)-301 Sumpter, one-story brick dwelling, post 1926
- 312-(C)-307 Sumpter, one-story cottage, 1920
- 313-(C)-309 Sumpter, one-story cottage, c. 1920
- 314-(C)-311 Sumpter, one-story cottage, c. 1920
- 315-(P)- Sherman Street, one-story frame building, 2nd Baptist Church, formerly Community House
- 316-(C)-314 Jackson, one-story cottage, c. 1920
- 317-(C)-312 Jackson, one-story cottage, c. 1920
- 318-(F)-573 Roosevelt Avenue, one-story brick store, post 1926
- 319-(C)-571 Roosevelt Avenue, one-story brick store, c. 1920
- 320-(F)-321 Mayo Avenue, one-story frame dwelling, post 1926
- 321-(F)-319 Mayo Avenue, one-story frame dwelling, post 1926
- 322-(C)-311 Mayo Avenue, one-story cottage, c. 1920
- 323-(C)-309 Mayo Avenue, one-story cottage, c. 1920
- 324-(C)-307 Mayo Avenue, one-story cottage, c. 1920
- 325-(C)-305 Mayo Avenue, one-story cottage, c. 1920
- 326-(C)-303 Mayo Avenue, one-story cottage, c. 1920
- 327-(C)-301 Mayo Avenue, one-story cottage, c. 1920
- || 328-(P)- West Badin Elementary School, <sup>two</sup>one-story brick (vacant), 1925
- 329-(I)- School Annex, c. 1950
- 330-(I)- three trailers, c. 1970

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 331-(F)-901 Sherman Street, one-story frame dwelling, post 1926
- 332-(F)-903 Sherman Street, one-story frame dwelling, post 1926
- 333-(C)-905 Sherman Street, one-story cottage, c. 1920
- 334-(C)-907 Sherman Street, one-story cottage, c. 1920
- 335-(F)-909 Sherman Street, one-story frame dwelling, post 1926
- 336-(C)-911 Sherman Street, one-story cottage, c. 1920
- 337-(F)-913 Sherman Street, one-story brick dwelling, post 1926
- 338-(C)-917 Sherman Street, one-story cottage, c. 1920
- 339-(C)-919 Sherman Street, one-story cottage, c. 1920
- 340-(C)-921 Sherman Street, one-story cottage, c. 1920
- 341-(C)-401-403 Lincoln Street, one-story duplex, c. 1920
- 342-(F)-320 Lincoln Street, one-story frame dwelling, post 1926
- 343-(F)-318 Lincoln Street, one-story frame dwelling, post 1926
- 344-(C)-316 Lincoln Street, one-story cottage, c. 1920
- 345-(F)-310 Lincoln Street, one-story cottage, c. 1920
- 346-(C)-310 Lincoln Street, one-story cottage, c. 1920
- 347-(C)-308 Lincoln Street, one-story cottage, c. 1920
- 348-(C)-306 Lincoln Street, one-story cottage, c. 1920
- 349-(C)-304 Lincoln Street, one-story cottage, c. 1920
- 350-(F)-238 Lincoln Street, one-story frame dwelling, post 1926
- 351-(C)-228-226 Lincoln Street, one-story duplex, c. 1920
- 352-(C)-224-222 Lincoln Street, one-story duplex, c. 1920
- 353-(C)-220-218 Lincoln Street, one-story duplex, c. 1920
- 354-(C)-216-214 Lincoln Street, one-story duplex, c. 1920
- 355-(C)-212-210 Lincoln Street, one-story duplex, c. 1920

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 356-(F)-208 Lincoln Street, one-story frame dwelling, post 1926
- 357-(C)-206 Lincoln Street, one-story cottage, c. 1920
- 358-(C)-204 Lincoln Street, one-story cottage, c. 1920
- 359-(F)-202 Lincoln Street, one-story frame dwelling, post 1926
- 360-(C)-201-203 Lincoln Street, one-story duplex, c. 1920
- 361-(C)-205-207 Lincoln Street, one-story duplex, c. 1920
- 362-(C)-209-211 Lincoln Street, one-story duplex, c. 1920
- 363-(C)-217-219 Lincoln Street, one-story duplex, c. 1920
- 364-(C)-221-223 Lincoln Street, one-story duplex, c. 1920
- 365-(C)-225-227 Lincoln Street, one-story duplex, c. 1920
- 366-(C)-229-231 Lincoln Street, one-story duplex, c. 1920
- 367-(C)-233-235 Lincoln Street, one-story duplex, c. 1920
- 368-(F)-912 Dewey Street, one-story frame dwelling, post 1926
- 369-(C)-906 Dewey Street, one-story cottage, p. 1920
- 370-(C)-902 Dewey Street, one-story cottage, c. 1920
- 371-(C)-902 Dewey Street, one-story cottage, c. 1920
- 372-(F)-228 Wayne Street, one-story frame dwelling, post 1926
- 373-(C)-218-216 Wayne Street, one-story duplex, c. 1920
- 374-(C)-212-214 Wayne Street, one-story duplex, c. 1920
- 375-(C)-208-210 Wayne Street, one-story duplex, c. 1920
- 376-(C)-204-206 Wayne Street, one-story duplex, c. 1920
- 377-(F)- Wayne Street, one-story frame dwelling, post 1926
- 378-(C)-203-205 Wayne Street, one-story duplex, c. 1920
- 379-(F)-229 Wayne Street, one-story frame dwelling, post 1926

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 380-(F)-815 Dewey Street, one-story brick church, post 1926
- 381-(C)-803-805 Dewey Street, one-story duplex, c. 1920
- 382-(P)- A.M.E. McDonald Church, one-story brick church, c. 1925
- 383-(I)-214 Mayo Street, two-story brick apartment, c. 1950
- 384-(C)-208 Mayo Street, one-story cottage, c. 1920
- 385-(C)- 206 Mayo Street, one-story cottage, c. 1920
- 386-(C)-202 Mayo Street, one-story cottage, c. 1920
- 387-(C)-200 Mayo Street, one-story cottage, c. 1920
- 388-(C)-203 Mayo Street, one-story cottage, c. 1920
- 389-(F)-205 Mayo Street, one-story frame dwelling, post 1926
- 390-(F)-209 Mayo Street, one-story cottage, c. 1920
- 391-(C)-206 Washington Street, one-story cottage, c. 1920
- 392-(C)-204 Washington Street, one-story cottage, c. 1920
- 393-(C)-202 Washington Street, one-story cottage, c. 1920
- 394-(C)-200 Washington Street, one-story cottage, c. 1920
- 395-(P)-701 Roosevelt Street, 1st Baptist Church, West Badin, one-story brick, c. 1925
- 396-(C)-703 Roosevelt Street, one-story cottage, c. 1920
- 397-(C)-705 Roosevelt Street, one-story cottage, c. 1920
- 398-(C)-707 Roosevelt Street, one-story cottage, c. 1920
- 399-(F)-604 Roosevelt Street, one-story dwelling, post 1926
- 400-(F)-700 Roosevelt Street, one-story dwelling, post 1926
- 401-(C)-706 Roosevelt Street, one-story cottage, c. 1920
- 402-(C)-708 Roosevelt Street, one-story cottage, c. 1920
- 403-(F)-712 Roosevelt Street, one-story frame dwelling, post 1926

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet


Item number

Page

- 404-(C)-714 Roosevelt Street, one-story brick structure, Fire Department Building, c. 1925
- 405-(C)-716 Roosevelt Street, one-story cottage, c. 1920
- 406-(C)-718 Roosevelt Street, one-story cottage, c. 1920
- 407-(C)-804 Roosevelt Street, one-story cottage, c. 1920
- 408-(C)-806 Roosevelt Street, one-story cottage, c. 1920
- 409-(F)-808 Roosevelt Street, one-story dwelling, post 1926
- 410-(C)-812 Roosevelt Street, one-story cottage, c. 1920
- 411-(C)-814 Roosevelt Street, one-story cottage, c. 1920
- 412-(C)-816 Roosevelt Street, one-story cottage, c. 1920
- 413-(C)-818 Roosevelt Street, one-story cottage, c. 1920
- 414-(F)-809 Marion Street, one-story frame dwelling, post 1926
- 415-(F)-805 Marion Street, one-story frame dwelling, post 1926
- 416-(C)-801 Marion Street, one-story cottage, c. 1920
- 417-(C)-715 Marion Street, one-story cottage, c. 1920
- 418-(F)-707 Marion Street, one-story dwelling, post 1926
- 419-(C)-705 Marion Street, one-story cottage, c. 1920
- 420-(C)-703 Marion Street, one-story cottage, c. 1920
- 421-(C)-607 Marion Street, one-story cottage, c. 1920
- 422-(C)-605 Marion Street, one-story cottage, c. 1920
- 423-(C)-603 Marion Street, one-story cottage, c. 1920
- 424-(F)-810 Marion Street, one-story dwelling, post 1926
- 425-(F)-808 Marion Street, one-story dwelling, post 1926
- 426-(C)- site of two frame cottages, c. 1920
- 427-(F)-708 Marion Street, one-story dwelling, post 1926

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet


Item number

Page

- 428-(F)-706 Marion Street, one-story dwelling, post 1926
- 429-(F)-612 Marion Street, one-story dwelling, post 1926
- 430-(C)-610 Marion Street, one-story cottage, c. 1920
- 431-(C)-608 Marion Street, one-story cottage, c. 1920
- 432-(C)-606 Marion Street, one-story cottage, c. 1920
- 433-(C)-604 Marion Street, one-story cottage, c. 1920
- 434-(C)-16 Sumpter Street, one-story cottage, c. 1920
- 435-(F)-8 Sumpter Street, one-story brick store, c. 1940
- 436-(P)-52 Roosevelt Street, movie theater, vacant, c. 1920
- 437-(C)-site of two frame cottages, c. 1920
- 438-(C)-site of three frame cottages, c. 1920
- 439-(C)-17 Sumpter Street, one-story cottage, c. 1920
- 440-(C)-15 Sumpter Street, one-story cottage, c. 1920
- 441-(C)-13 Sumpter Street, one-story cottage, c. 1920
- 442-(C)-7 Sumpter Street, one-story cottage, c. 1920
- 443-(C)-5 Sumpter Street, one-story cottage, c. 1920
- 444-(C)-2303-2308 Roosevelt Street, five unit commercial building, one-story brick, c. 1920
- 445-(F)-407 Roosevelt Street, one-story brick commercial building, post 1926
- 446-(C)-305 Jackson Street, one-story cottage, c. 1920
- 447-(C)-307 Jackson Street, one-story cottage, c. 1920
- 448-(C)-309 Jackson Street, one-story cottage, c. 1920
- 449-(C)-315 Jackson Street, one-story cottage, c. 1920
- 450-(F)-314 Grant Street, one-story frame dwelling, post 1926

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page

451-(C)-312 Grant Street, one-story cottage, c. 1920

452-(C)-309 Grant Street, one-story cottage, c. 1920

453-(C)-307 Grant Street, one-story cottage, c. 1920

454-(F)-301 Grant Street, one-story brick dwelling, post 1926

# 8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input checked="" type="checkbox"/> landscape architecture	<input checked="" type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input checked="" type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input checked="" type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		

Specific dates N/A Builder/Architect N/A

**Statement of Significance (in one paragraph)**

The town of Badin and the Narrows Dam along the Yadkin River represent important developments in the history of engineering, industry, and community planning in North Carolina. The Narrows Dam was the largest hydro-electric facility ever built in North Carolina and highest concrete dam constructed in the country when it was completed in 1917. The chief economic activity of the town--the production of aluminum ingots--introduced a new industrial process into piedmont North Carolina and began a pattern of industrial diversification in a state traditionally dominated by the textile, tobacco, and furniture industries. The town of Badin, planned by a French company and completed by the Aluminum Company of America, is distinct both for the quality of its housing for workers and for its racially integrated work force.


Criteria for Assessment:

A. Badin's history is associated with the growth of industry in North Carolina's Piedmont and with the diversification of the industrial base of the region; it is also illustrative of the role of outside investment in North Carolina.

B. Badin is associated with individuals prominent in local industrial history--such as E.B.C. Hambley who conceived of the hydroelectric dam at the Narrows of the Yadkin River--and with individuals of national and even international importance--such as Andrew Mellon who founded ALCOA and located a branch of its operation at Badin.

C. Badin's architecture represents a distinct form of company town, one designed by a foreign company and completed by a Northern corporation, offering a revealing contrast to the typical mill village of the Piedmont.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 1


"The River Yadkin," wrote historian William Winterbotham in 1796, "is reduced . . . about twenty-five miles to the southward of (Salisbury), to the width of eighty or one hundred feet. For two miles it is narrow and rapid . . . (and) in this narrow part, shad are caught in the spring of the year by hoop-nets . . . as fast as the strongest men are able to throw them out. Perhaps there is not in the United States a more eligible situation for a large manufacturing town."<sup>1</sup> A full century passed before a plan emerged to harness the industrial potential of the Narrows. Badin, the industrial community that grew up at the Narrows, owes its existence to this ambitious plan for regional development in the Piedmont.

An English mining engineer, Egbert Barry Cornwall Hambley, first proposed the idea to develop the Narrows in 1898. Hambley had settled in Salisbury in 1887 after working as a special engineer for several successful engineering firms in London. His work took him around the world and introduced him to important business contacts as well as the latest technological innovations. Hambley's connections with British industrialists and capitalists helped him attract capital to the Salisbury region. From 1887 to 1890 he served as consulting engineer for no less than eight British mining companies all located in North Carolina, and was managing director for a company in Montgomery County. During this same period, he also became identified as a promoter of business and industry of various sorts in the Salisbury vicinity, including a railroad, a utility company, a cotton mill, and a bank. One contemporary claimed that "(Hambley) has been more successful than any other resident of the State in inducing men with large means residing elsewhere to make investments in North Carolina."<sup>2</sup>

In the late 1890s, Hambley turned his attention to the general problem of regional development and specifically to the question of providing power for the burgeoning industrial activity of North Carolina's central piedmont. He established contact with several investors in New York and Pennsylvania. In 1898, reports of a company organized to develop the water power at Yadkin Falls began to appear in local newspapers and trade journals. Early in the following year, Manufacturer's Record reported "a party of Northern capitalists are inspecting the falls of the Yadkin in Stanly county. They propose the establishment of an electric power plant for the distribution of power to Albemarle, Salisbury and Concord."<sup>3</sup>

Only a few decades earlier such a proposal would have been unthinkable. Three major problems preventing such a project were geography, lack of technology, and insufficient capital. The site of the proposed dam was more a "natural curiosity" than a candidate for manufacturing or a source of electric power. For the better part of the nineteenth century, local residents had used the area to "fish for shad or rock fish with small nets affixed to staffs."<sup>4</sup> The single most interesting feature of the area was the stretch of river just above the falls known as "the Narrows". This feature was a deep gorge through which the Yadkin ran for three and one half miles.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8


Page 2

At the upper end, before reaching the Narrows, the river is nearly or quite 1,000 feet wide, from which it suddenly contracts, entering a narrow ravine between the hills, which rise abruptly on either wide with rocky and almost perpendicular banks and through which it pours with great violence . . . No description can do justice to this place which is one of the most wonderful spots that can be found in the South.<sup>5</sup>

For all its splendor, the Narrows posed enormous physical problems for potential development. Although it would be possible to build a dam above the Narrows, "no one would think of locating a large establishment right in a gorge of the mountains, in such an inaccessible place and on the rocky bank of a river, where it is liable to overflow in times of high water." The cost of constructing a canal along the Narrows or around the hills would be prohibitive and there was little room along the banks below the Narrows for a mill or manufacturing village. A census report in 1880 concluded that "but a very small proportion of the total power at this place is practically available." Even as late as 1899, the Manufacturer's Record acknowledged that the location was "one of the finest in the South, but its remoteness from transportation lines has heretofore been one of its greatest drawbacks."<sup>6</sup>

The development of long-distance power transmission helped overcome the problems of geographical isolation. The Narrows and Falls of the Yadkin offered little to potential investors as the site of a single manufacturing unit, but the area attracted renewed interest as a possible source of electric power in the last decade of the nineteenth century. By this time, electric power transmission had gained widespread acceptance as a safe, economic, and convenient means of driving machinery in manufacturing facilities. The cost of installing, maintaining, and operating electrical plants compared favorably with steam power plants, and the clean energy of electricity was particularly attractive in comparison to the grimy conditions associated with steam power. The first hydroelectric facilities in the United States had appeared in New England in the early 1890s with plants designed to run machinery at the site of the power dam. In the mid-1890s, power companies throughout the country constructed dams and power plants that could transmit electrical power over longer distances. During the latter part of 1895, for example, the Anderson Water, Light, and Power Company in Anderson, South Carolina began to transmit electricity generated by water power from the Seneca River over a distance of six miles, the first significant distance transmission plant in the South. In 1898, the Fries Power and Manufacturing Company constructed North Carolina's first hydroelectric facility to drive textile mills, streetcars, and small manufacturing plants in the adjoining towns of Winston and Salem. The Fries dam and powerhouse, (operated today by Duke Power Company) located at Idols on the Yadkin River several miles north of the Narrows, transmitted electric power thirteen and one half miles to a substation in Salem. In that same year, Joseph A. Holmes, state geologist for North Carolina, offered the opinion that the Narrows and Falls of the Yadkin might indeed be suitable for similar development: "A dam at the lower end," Holmes speculated,

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number 8

Page 3


. . . would back water but little above the upper end of the gorge and would flood hardly ten acres of cultivable land. The bed and banks of the river are of solid rock, and there is also at hand an ample supply of stone suitable for the construction of such a dam. Immediately below this point the river widens out to such an extent that there would be but little loss of power from high water. From this point the power could be transmitted by electricity to suitable points on the Salisbury and Norwood branch of the Southern railroad, about five miles distant, where manufacturing establishments could be located or the power could be transmitted to Lexington, Salisbury, Concord, or Charlotte . . .<sup>7</sup>

Holmes's proposal closely followed the plan actually devised by E. B. C. Hambley. Through his experience as an engineer and his familiarity with the Yadkin region, Hambley had recognized the possibility of long distance electric power transmission and the potential of the Narrows and Falls of the Yadkin as a power source. His ability to attract large quantities of investment capital was perhaps equally important to his appreciation of the natural resource and the new technology. He had organized the North Carolina Power Company in 1899 with a \$5 million capital stock plus \$2.5 million in bonds. At the same time, he engaged the interest of George I. Whitney, a financier from Pittsburgh and a member of one of that city's most prestigious brokerage houses, Whitney and Stephenson. More important, Whitney was a director in Union Trust--the Union Transfer and Trust Company--and a financial confidant of Andrew Mellon, builder of a fabulous financial and industrial empire. In 1898, Mellon and Whitney had engineered the consolidation of most coal mines in the Monongahela River valley, so that by 1899, their company, River Coal--Monongahela River Consolidated Coal and Coke Company--controlled ninety-six out of one hundred and two mines in the valley and forty-four boat companies. For his work in this prodigious undertaking, Whitney received large blocks of stock in seven subsidiary operations and generous loans from Union Trust, the bank created and dominated by his partner Mellon.<sup>8</sup> With his wealth steadily increasing and his desire for his own industrial empire growing, Whitney purchased controlling interest in Hambley's North Carolina Power Company in 1899 and formed the Whitney Development Company. E. B. C. Hambley served as general manager of the Whitney Company's operations in North Carolina and established his headquarters in the Gold Hill mining district, where a subsidiary of the development company, called the Whitney Reduction Works, operated two mines in northwest Cabarrus County.

The reduction works in the Gold Hill mining district was only part of the Whitney Company's bold and far-reaching plan for resource development in the central Piedmont, a plan which included promotion of mining, manufacturing, real estate, and utilities. In addition to the Whitney Reduction Works, the company created other wholly-owned and operated subsidiary enterprises including the Rowan Granite

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number 8

Page 4

Works at what became Granite Quarry, the Barringer Gold Mining Company in Stanly County, the Yadkin Land Company, the Yadkin River Electric Power Company, the Yadkin Mines Consolidated Company, and the Virginia Copper and Land Company. These companies were to operate independently and also to serve as springboards for the creation of new manufacturing and power outlets throughout the region. Through the subsidiaries, the Whitney-Hambley partnership planned the construction of cotton mills and other manufacturing plants. They secured right-of-way for power lines as far away as Knoxville, Tennessee and prepared to sell electricity to those companies they did not own outright.<sup>9</sup>

The pivotal element in the Whitney Company's plan was the hydroelectric power dam four and one half miles above the Narrows of the Yadkin. Although the dam went through several design phases, the final blueprint called for a granite structure thirty-five feet high and 1,100 feet long, designed to create a 27,000 horsepower output. A five-mile canal would connect the dam to a power plant on the river just below Palmer Mountain. The company constructed a spur line from the dam site through New London, to its quarry in Rowan County, and on to its mines in Cabarrus County near Gold Hill. Hundreds of workers, including miners from Gold Hill as well as Sicilian masons, arrived to build the dam out of huge granite blocks, and company engineers laid out streets and boulevards for what was to become the manufacturing town of Whitney located at the construction site. The company had purchased nearly 30,000 acres in Rowan, Cabarrus, Stanly, Davidson, and Montgomery counties.<sup>10</sup>


The public reception for the Whitney project was understandably warm. Manufacturer's Record led the early rounds of approval, noting that by May of 1899, the company had raised several million dollars for the erection of the great dam and power plant,

. . . while a minimum of \$500,000 is set aside for the building and equipping of a strictly modern cotton mill to be operated entirely by electrical power. It is intended to be the pioneer mill of the kind in the South, the revolutionizer of the cotton manufacturing industry. It will have no expensive engine and no smokestack and no boiler plant. The company is doing nothing on paper. It will be the new mill . . . Does not all this signify wonderful possibilities for the manufacturing and industrial interests of this section of North Carolina?<sup>11</sup>

In the months and years that followed, the Whitney-Hambley plan unfolded with announcements of streetcar companies, light companies, and new construction sites. Local newspapers greeted each new development with increasing enthusiasm. A Lexington journal, for instance, spoke of a "revolution of manufacturing" and predicted that Whitney and Hambley would make the Piedmont the garden spot of North Carolina, comparable to the great industrial places of New England. "The master-minds at Whitney," continued the report, "are engaged in carrying out a giant scheme to grapple with and subdue elemental nature, forcing her with many inventions to lend her untamed energy, wasted for ages, to the direction of human intelligence, that much good may result to the world of man." The harnessing of the power of the Yadkin River, observed a Concord paper, promised so much for industrial

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number 8

Page 5

enterprises in the Piedmont, while the Charlotte Chronicle, in April, 1906, noted that the enormity of the project was beyond the comprehension of ordinary citizens:


The public has not yet obtained an adequate idea of the extent of the work . . . . This company will not only be sending electricity into Charlotte and other towns . . . . but will be operating factories of its own and for other people in what will be the model manufacturing town in the United States, on the banks of the Yadkin.

Despite the infusion of capital investment and an enthusiastic public, the Whitney Company floundered and ultimately failed within its first decade of existence. The first setbacks for the company came in the mines at the Gold Hill district. An accident at the Barringer mine in the summer of 1904 left eight men dead and the company in debt to families and creditors. The Barringer, the first of North Carolina's deep mines, never reopened. By 1905, the Whitney properties in Cabarrus County, the old McMackin and Isenhour mines were likewise filled with water.<sup>12</sup> At the dam construction site along the Yadkin, outbreaks of typhoid severely depleted the labor force each summer. Captain Hambley himself contracted typhoid in the summer of 1906, and after a prolonged illness, he died on August 13 at the age of forty-four. His death shocked the business and industrial community of North Carolina. In an editorial in the Charlotte Observer, D. A. Tompkins called Hambley's death "a most deplorable event." "Few men," Tompkins continued, "have done more for (North Carolina) in a material way, and his value to it and the extent of the loss it has sustained in his death are beyond estimate."<sup>13</sup> The mine disaster and death of chief engineer Hambley were serious setbacks for the Whitney operation but not nearly as devastating as the blow it suffered in 1908 when Andrew Mellon forced George Whitney into a disastrous sale of Whitney's major coal mining stocks which ultimately led the Whitney Company into bankruptcy in 1910.<sup>1</sup>

In 1912, the Southern Aluminum Company, a subsidiary of the French company, L'Aluminum Francasise, purchased the Whitney property along the Yadkin. The French were seeking a cheap source of electrical power to produce aluminum. Ever since the development of the electrolytic process patented by Charles Martin Hall in 1886, this lightweight metal had become an essential ingredient in the growing electrical and building industries. Southern Aluminum abandoned the original Whitney dam site and decided to build its power facility directly at the Narrows a few miles downstream. The projected two hundred foot high dam would provide power to a reduction plant adjacent to the dam on the Stanly County side of the river. In the spring of 1913, the company cleared ten acres of land, poured large footings and erected steel columns. Company engineers drew up plans for a water filter plant, a sewage disposal plant, and a company town which included a sewer system, workers' housing, and a clubhouse. The town would be called Badin after the company's president, Adrien Badin, and its design would complement the geographical setting of the site.

By the time of the outbreak of the First World War in August, 1914, Southern Aluminum had completed two by-pass tunnels and some building and machine shop foundations, as well as the clubhouse, workers' housing, and the water system in Badin. The hostilities in Europe, however, precipitated the end of the construction project.

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 6

Many company engineers and technicians were reservists in the French army and left Badin for duty in France. More importantly, Southern Aluminum found its lines of credit in Europe had been redirected to support the war effort. President Badin turned to northern bankers and investment houses for assistance but found no support in New York, Boston, Philadelphia, or Cleveland. Only the Mellon interests in Pittsburgh expressed an interest in the desperate company in North Carolina. By this time, Mellon's aluminum monopoly, the Aluminum Company of America (Alcoa) was predominant among national producers and had reached a point of nearly perfect vertical integration. The company controlled the nation's chief supply of bauxite--the ore from which aluminum is made--in Arkansas, Georgia, Alabama, and Tennessee. Alcoa could hardly mask its intentions to control the world production and marketing of this valuable metal, especially with the outbreak of war promising new and spectacular profits. The French company in North Carolina posed only a mild threat to this campaign, but the Pittsburgh firm would not pass up an opportunity to purchase a half-finished plant and company town at a bargain price. Southern Aluminum sold out to Alcoa in November of 1915 at a loss of one million dollars.<sup>15</sup>


The purchase of the North Carolina property was a stroke of fortune for Alcoa. The company now controlled an impressive source of cheap electrical power at a site within reasonable distance from its southern bauxite mines. Instead of producing finished aluminum, the Badin plant would manufacture only pig aluminum which would be sent to finishing plants in Pennsylvania and New Jersey. Early in 1916, Alcoa's subsidiary, the Tallassee Power Company, began work to complete the dam and smelter. By August, the smelter was producing pig aluminum using power purchased from the Southern Power Company. It was another year before the Narrows dam itself generated electrical power. The construction site reflected an awesome display of men, materials, and machinery. An enormous labor force, half of whom were convicts under contract from the state, camped at the dam site. The company tapped a national network of supplies and equipment--cement from Virginia, derricks from Minnesota, mixers and crushers from Wisconsin and Illinois--to complete the project.

Once again, the attention of the southern industrial and local press riveted on the ambitious work at the Narrows of the Yadkin. Manufacturer's Record called it "a gigantic, impressive development." The Greensboro Daily News noted that Narrows was the

. . . . largest undertaking of its kind ever attempted in North Carolina . . . .  
It is said by many to be one of the finest pieces of construction work in the United States, and so tremendous is its appearance, a veritable mountain of concrete, that one is reminded that it has more the appearance of being the handiwork of the Supreme Architect of the Universe than that of human hands.<sup>16</sup>

For many North Carolinians of the period, a hydroelectric dam and its technology signaled the dawn of a new age without natural restrictions. Bion H. Butler, a well-known North Carolina journalist, called the Narrows Dam project "a revelation of what men are doing with natural forces." Butler found the sheer magnitude of the plan staggering. "After the tunnels are closed and the head is raised . . ." he wrote,

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 7

. . . and the power houses are completed and the Allis-Chalmers wheels and generators are installed, the upper end of the tunnels will be blocked up with rock and cement, and the gorge from the dam up will give way to a lake that will drown out the river entirely. The river will stop.<sup>17</sup>


On June 17, 1917, the final closure in the dam was made and a month later, Badin Lake had reached a sufficient level to begin generating power--nearly 125,000 horsepower--to run the plant which included pot rooms, a carbon plant, and machine shops and the village. Badin Works employed one thousand workers, black and white, many of whom were veterans of the Whitney construction and mining projects. "Not only North Carolina but the entire South will be benefited by this great development," observed the Manufacturer's Record. "The completion of the plant will give to the South leadership in the aluminum industry . . . (and) mark a very important event in the broadening of Southern industrial development, and especially in the manufacture of the finer class of goods requiring skilled labor."<sup>18</sup>

The company town of Badin emerged over a ten year period that coincided with the construction of Alcoa's power facilities and reduction works. The French company, L'Aluminum Francaise, laid out the town and began construction late in 1913. A New York architectural firm, Pierson and Goodrich, provided the design for the town and most of the company buildings and residences. During this time, the French completed only a few buildings including a main office, a garage, a laboratory, a club house for single male employees and visitors, and a residence for the plant manager. They constructed several public service systems including water and sewer lines, electrical distribution lines, and a filter plant.<sup>19</sup>

In addition, the French managed to complete single family residences along Henderson Street and began work on approximately 150 apartments within the original townsite bounded by what is now Spruce Street on the east, Badin Lake on the north, Honey Ditch on the south, and the main highway (NC740) on the west. The French suspended this construction activity shortly after the start of hostilities in Europe in 1914 and further development at the townsite was not resumed until 1916. During the first year that Alcoa controlled the properties at Badin, the company concentrated most of its efforts at the dam site at the Narrows. Residential construction consisted chiefly of shanties and temporary structures for the scores of laborers that had been recruited from rural areas, prisons, and foreign countries.<sup>20</sup>

By the end of 1916, the company turned its attention to continuing the development of the company town at Badin. The first step in this redevelopment activity was to complete the apartments begun by the French three years earlier. Bungalows along Tallassee Avenue and cottages on Pine Avenue were built. A woman's annex to the main club house provided additional housing for teachers and office staff.<sup>21</sup> Public buildings, including a hospital, a twenty room school, and a theater, were also constructed at this time. The hospital, a two-story, twenty-five bed facility, boasted a

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 8

dining room, a kitchen, a laundry, fifteen rooms for patients, three offices, an operating room, an x-ray room, scrub room, two waiting rooms, sun parlors, and porches. The theater was perhaps the most dominant building in the town and was reputed to be the largest of its kind between Richmond and Atlanta. It served as a cultural and social center for the community until its demolition early in 1959.<sup>22</sup>


A series of brick commercial buildings, designed by the Pittsburgh firm of G. H. Giesey Associates, was constructed to serve the small industrial community that had at last been permanently settled in the fall of 1917. The Giesey firm also provided the design for many small bungalows built by the company after World War I. The original designs for these structures called for four to seven room cottages in the white section of Badin, while in the black section, West Badin, Giesey's designs called for three and four room cottages.<sup>23</sup> A five room house sold at that time for nearly \$1500 while monthly rents varied from \$4.50 for cottages to \$6-\$10 a month for apartments.<sup>24</sup>

The last residential development at Badin during Alcoa's first decade was in West Badin or "The Quarters," a section reserved for black workers and their families. The company had made a special effort to attract black workers and aimed much of its recruiting literature to the southern rural black audience. "Badin offers," said a 1920 company brochure, "greater economic, educational, moral, and social development to the colored laborer than any other community in the United States." As proof of this statement, the company offered illustrations of a church erected in the black community for \$10,000 and the proposed brick school, dedicated in 1925 by Andrew Mellon and other dignitaries, both black and white. The company provided a black physician, nurse, and welfare worker for social services for its employees and generally offered duplicate services found in the white community.<sup>25</sup> Naturally, the company maintained clear lines of distinction between the races. Blacks generally worked in less skilled occupations and were not offered supervisory positions at the plant. Nevertheless, living conditions, wages, and cultural opportunities for black workers and their families were considerably greater at Badin than at other company towns throughout the South.

Unlike most company towns in the South, Badin was truly a melting pot of workers from many backgrounds. Naturally, large numbers of white and black workers had been poor farmers from the southern Piedmont; others, trained in masonry and construction trades had been recruited from Italy; many of the engineers and plant supervisors migrated from northern technical institutes or corporate headquarters in Pittsburgh. One of those engineers, Mr. A. J. Rice, described the scene in Badin when he arrived in October, 1917:

"We rocketed along in the small train, following the outlines of a channel or canal, on a roadbed just a few feet above the water, past some higher ground on the river side of the track, which I later learned was known as Palmer Mountain. Turning a long curve to the right, I saw across the water of an inlet, a great number of shacks, looking more like bee-hives than houses, scattered over a hillside. This was another eye-opener to me, which I later learned to be the Hardaway Construction

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 9

Company's former camp. A mile or so further we reached the station of Badin, a typical small railroad station with a horse-drawn "hack" for passenger transportation available for anyone who wished to ride rather than walk to his destination."<sup>26</sup>

Alcoa divided its Badin facility into two departments, electrical and mechanical, and two plants, carbon and aluminum. The electrical department was responsible for the installation and maintenance of motors, cranes, alternating current generators, transformers and rotary converters as well as the repair of motors and wiring. This department also erected and maintained large power transmission lines, street light systems, and telephones. The mechanical department designed, produced, and erected steel buildings, repaired machinery, and fitted pipes and iron castings.


The carbon plant manufactured carbon electrodes necessary in the production of aluminum by mixing finely ground coke with tar or pitch before being pressed into blocks and baked. The aluminum plant housed the furnace where the production of aluminum took place by reducing the ore under extremely high temperatures. Because reheating a pot after a period of cooling is time-consuming and expensive, the operation of the aluminum plant was--and still is--continuous, requiring three eight-hour shifts.<sup>27</sup>

A small business district grew up around the aluminum plant by the early 1920s. One of the first major buildings completed was called the Commercial Block at the corner of Pine Street and Yadkin Court. Alcoa built the building to furnish space for a shoe store, a men's clothing store, a grocery, and a meat market. The company's Property Office and drafting room, a ladies' clothing store and hat shop, a photographic studio, and a residential apartment occupied the second floor. Across the street stood a frame building with several "stalls" for a tailor shop, a cobbler, and a notions store. This building site is now occupied by the union hall of the Aluminum Workers of America.<sup>28</sup>

The union had won certification by a narrow margin in April, 1940, and built on that core of support over the next twenty years. Today, wage and benefit plans for Alcoa's workers are decidedly superior to those offered workers in nearby textile mills and furniture factories. Until the formation of the union, the forceful personality of S. A. Copp, superintendent of Badin from 1923 to 1946 dominated the community. Copp's retirement came at a time when the union had become a stronger presence and when company policy no longer required a self-supporting company town in Badin.<sup>29</sup> The emergence of modern labor-management relations coincided with the decline of the company town.

The Narrows Dam was to be the first of four hydroelectric facilities constructed by Alcoa along the Yadkin River. A dam at Yadkin Falls, 112 feet high with a capacity of around 29,500 kilowatts was completed in 1919. In December, 1927, the High Rock power project went "on stream" with a dam 100 feet high and a power plant capacity of 33,000 kilowatts. The fourth and final dam, at Tuckertown, was not constructed until the early 1960s after protracted negotiations with the Federal Power Commission. This dam generates around

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet

Item number 8

Page 10


42,000 kilowatts. The entire power complex produces over 200,000 kilowatts and covers over 23,000 reservoir acres.<sup>30</sup>

Alcoa maintained the same facility at Badin for over forty years until the late 1950s when it became apparent that the plant and equipment had become outdated and inefficient. The modernization called for complete dismantling of the original eight potlines and installation of two modern 50,000 ton potlines at a cost of \$20 million. This work was completed in 1966 and resulted in a doubling of production for the Badin Works.

Even with the introduction of modern equipment, the basic function of Badin Works has not changed. It begins with alumina, a powdery substance refined from bauxite. Alcoa's bauxite is now mined in Surinam, South America and shipped to a refinery in Mobile, Alabama. At Badin Works, the alumina from the Mobile plant is dissolved in a molten mineral called cryolite. An electric current is passed through this solution so that oxygen is given off from the alumina, leaving aluminum to settle at the bottom of large electrolytic "pots". Molten aluminum is removed from the pots every twenty-four hours and taken to the Ingot Department where it is cast in ingots. The ingots are shipped to Alcoa plants worldwide for further processing. The production of aluminum ingots remained the primary activity of Badin Works until 1978 when the company announced plans to construct a \$10 million facility for a continuous casting process which would produce heavy gauge sheet aluminum bringing the melted aluminum one step closer to a finished product.<sup>31</sup>

The productivity and prosperity of the Badin plant did not result in the expansion or enhancement of the company town at Badin. On the contrary, the fortunes of the commercial and residential districts began a sharp decline evident by the middle 1920s. A decline in orders after the first World War led to layoffs of many workers and a reduction in the local population. The company constructed no new housing after 1925. Of greater importance was the general dispersal of the Alcoa's working population with the increased accessibility of the automobile and the improvement of rural roads. In addition, a decline in new construction work and the introduction of labor-saving equipment placed a limit on the need for new workers in the area. By the early 1930s, many of the smaller company cottages were sold to be dismantled and removed. In the white section of Badin, this cleared area soon became the location of newer housing built privately after World War II. Much of the land remains vacant today. The same pattern developed in West Badin so that by 1965, Alcoa owned only one house in the white section and a handful of cottages in West Badin.<sup>32</sup> Today, Alcoa recruits workers from a five county area and the population of Badin has declined from 5000 in 1926 to around 1500 today. Over 1000 residential structures stood in Badin in 1926 while only around 650 are standing today, most of those built before 1926 by the company.<sup>33</sup> Even more dramatic than the decline of the residential section has been the disappearance of the commercial and cultural facilities in Badin. Symbolic of this decline was the demolition of the Badin Theater in 1959. A United States post office stands on its site.<sup>34</sup>

# National Register of Historic Places Inventory—Nomination Form



Continuation sheet


Item number 8

Page 11

In recent years, Alcoa has purchased various commercial structures along Falls Road and demolished these buildings for parking lots to accommodate its 800 workers, most of whom commute from nearby towns and rural areas. As long as the aluminum plant continues to operate, and there are certainly no plans to suspend operations, some sort of a settlement will continue in Badin. However, the village is today occupied chiefly by Alcoa retirees. Its population has decreased over the past twenty years and its commercial base has almost vanished. The growing concern among residents and those who want to preserve the little community is that "the city by the lake" could revert once again to a sort of wilderness in the future.

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page

FOOTNOTES --

<sup>1</sup>Salisbury Evening Post, 14 April 1977.

<sup>2</sup>A. J. Rice, "Recollections of Early Badin," (unpublished, 1978), 14; hereinafter referred to as Rice, "Recollections."

<sup>3</sup>Rice, "Recollections," 5.

<sup>4</sup>Rice, "Recollections," 14.


<sup>5</sup>Rice, "Recollections," 10-11.

<sup>6</sup>"Tarheel Alcoan," XIII, No. 3, (May-June, 1975).

<sup>7</sup>Badin Bulletin, (August, 1920).

United States Department of the Interior  
Heritage Conservation and Recreation Service

National Register of Historic Places  
Inventory—Nomination Form



Continuation sheet

Item number

Page

FOOTNOTES --

<sup>1</sup>William Winterbotham, An Historical, Geographical, Commercial and Philosophical View of the United States of America, and of the European Settlements in America and the West Indies, (Tiebout & O'Brien, New York; 1796), Vol. III, P. 201.

<sup>2</sup>Charlotte Observer, 14 August 1906.

<sup>3</sup>Manufacturer's Record, 27 January, 6 May 1898.

<sup>4</sup>Seventh Census, 1850: Montgomery County, Mortality Schedule.

<sup>5</sup>U. S. Department of the Interior. Tenth Census of the United States, 1880, XVI, 60, hereinafter referred to as Tenth Census.

<sup>6</sup>Tenth Census, 60.

<sup>7</sup>Joseph A. Holmes, Waterpowers of North Carolina (Raleigh: Edwards and Broughton, 1899), 180-181.

<sup>8</sup>Harvey O'Conner, Mellon's Millions (New York: John Day Company, 1933), 56, 65ff; hereinafter referred to as O'Conner, Mellon's Millions.

<sup>9</sup>Brent D. Glass, "Egbert Barry Cornwall Hambley," William S. Powell, ed., Dictionary of North Carolina Biography; (Chapel Hill: University of North Carolina Press, forthcoming), Vol. III.

<sup>10</sup>Glass, "E. B. C. Hambley," and Concord Times, 28 September 1906.

<sup>11</sup>Manufacturer's Record, 5 May 1899.


<sup>12</sup>The Dispatch (Lexington, N.C.), 14 February 1906; Concord Times, 20 April 1906; quotation from the Charlotte Chronicle is taken from the Concord Times, 27 April 1906; Salisbury Post, 26 September 1965; Richard Knapp and George Stinagle, "Preliminary Report on Gold Mining Technology," (unpublished, 1974), 180.

<sup>13</sup>Charlotte Observer; 14 August 1906.

<sup>14</sup>O'Conner, Mellon's Millions, 76.

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number

Page

<sup>15</sup>C. Vann Woodward, Origins of the New South (Baton Rouge: Louisiana State University Press, 1951), 305; O'Conner, Mellon's Millions, 91-92.

<sup>16</sup>Greensboro Daily News, 1 July 1917.

<sup>17</sup>News and Observer (Raleigh), 10 February 1917.

<sup>18</sup>Manufacturer's Record, 4 November 1917.

<sup>19</sup>Badin Carolinian, III, (March 1954), 4-6.

<sup>20</sup>Salisbury Post, 26 May 1974.

<sup>21</sup>Tallassee Power Company files, property of the Stanly County Historic Properties Commission.

<sup>22</sup>Stanly News, August 16, 1940.

<sup>23</sup>A. J. Rice, "Recollections of Early Badin." (unpublished, 1978), 14; hereinafter referred as to Rice, "Recollections."

<sup>24</sup>Badin Bulletin, September, 1920.

<sup>25</sup>"Prospectus for Badin," (n.p., n.d.) North Carolina Collection.

<sup>26</sup>Rice, "Recollections," 2.

<sup>27</sup>Rosemarie Hester, "Badin, North Carolina," (unpublished, 1980), Southern Oral History Program, University of North Carolina-Chapel Hill, 16, hereinafter referred to as Hester, "Badin."


<sup>28</sup>Rice, "Recollections," 13.

<sup>29</sup>Hester, "Badin," 14-15.

<sup>30</sup>Rice, "Recollections," 13.

<sup>31</sup>Stanly News and Press (Albemarle), June 13, 1980.

United States Department of the Interior  
Heritage Conservation and Recreation Service  
**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number

Page

<sup>32</sup>Rice, "Recollections," 14.

<sup>33</sup>Sanborn Insurance Company, Badin, 1926.

<sup>34</sup>Charlotte Observer, December 11, 1958, (In the mid-1950s Alcoa divided the Carolina Aluminum Company, formerly the Tallasse Power Company, into two separate corporate entities - Yadkin, Inc., which operates the hydroelectric facilities and Badin Works of Alcoa which is responsible for the aluminum plant, the carbon plant and other production facilities).

## 9. Major Bibliographical References

See continuation sheet.

## 10. Geographical Data

Acreeage of nominated property See continuation sheet

Quadrangle name Badin and New London

Quadrangle scale 1:24000

UMT References See continuation sheet.

A 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

B 

--	--	--	--	--	--	--	--	--	--

  
Zone Easting Northing

C 

--	--	--	--	--	--	--	--	--	--

D 

--	--	--	--	--	--	--	--	--	--

E 

--	--	--	--	--	--	--	--	--	--

F 

--	--	--	--	--	--	--	--	--	--

G 

--	--	--	--	--	--	--	--	--	--

H 

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

See continuation sheets.

List all states and counties for properties overlapping state or county boundaries

state N/A code county N/A code

state code county code

## 11. Form Prepared By

name/title Brent D. Glass and Pat Dickinson

organization Stanly County Properties Commission

date May, 1981

street & number 112 Third Street

telephone 983-1623

city or town Albemarle

state N. C.

## 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national  state  local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the Heritage Conservation and Recreation Service.

State Historic Preservation Officer signature

*William S. Price, Jr.*

title State Historic Preservation Officer

date April 8, 1982

For HCRS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register


Attest:

date

Chief of Registration

**United States Department of the Interior  
Heritage Conservation and Recreation Service**

**National Register of Historic Places  
Inventory—Nomination Form**



Continuation sheet

Item number

Page

BIBLIOGRAPHY --Badin Bulletin, 1919-1922.Badin Carolinian.Charlotte Observer.Concord Times.The Dispatch (Lexington).Glass, Brent. "E. B. C. Hambley" from Powell, William, ed., North Carolina Biographical Dictionary; III. Chapel Hill, University of North Carolina Press, forthcoming.Greensboro Daily News.

Hester, Rosemarie, "Badin, N.C.," n.p. 1980. Southern Oral History Program, UNC Chapel Hill.

Holmes, Joseph. Waterpowers of North Carolina. Raleigh, Edwards and Broughton, 1899.Manufacturer's Record (Baltimore).O'Conner, Harvey. Mellon's Millions, New York, John Day Company, 1933.News and Observer (Raleigh).

Prospectus, Tallassee Power Company, Badin, N.C.; n.d.

Rice, A. J. "Recollections of Early Badin," n.p. 1977.

Salisbury Evening Post.Sanborn Map Company, Badin, 1926.

Seventh Census of the United States, 1850. Montgomery County, Mortality Schedule.

Stanly News.Stanly News and Press.Tarheel Alcoan.U.S. Department of the Interior, Tenth Census, 1880, XVI, Washington, D.C.Winterbotham, William. An Historical, Geographical, Commercial and Philosophical View of the United States of America, and of the European Settlements in America and the West Indies. New York, Tiebout & O'Brien, 1796.Woodward, C. Vann. Origins of the New South, Baton Rouge; Louisiana State University Press, 19

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received _____
date entered _____

Continuation sheet      Geographical Data      Item number      10      Page      1

Narrows Complex - approximately 72 acres

Badin Quadrangle

Zone 17      Scale 1:24000

A 17 581940/3919780

B 17 582520/3920030

C 17 582740/3919430

D 17 582420/3919240

Badin Historic District - approximately 170 acres

Badin Quadrangle

Zone 17      Scale 1:24000

A 17 580220/3918330

B 17 581470/3918440

C 17 580840/3917500

D 17 580400/3917460

E 17 579780/3917800

West Badin Historic District - approximately 84 acres

Badin and New London Quadrangles

Zone 17      Scale 1:24000

Badin Quadrangle

A 17 579780/3919200

B 17 579840/3918380

New London Quadrangle

C 17 579420/3918050

D 17 579050/3918640

E 17 579440/3919080

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

Continuation sheet

Geographical Data

Item number 10

Page 2

VERBAL BOUNDARY DESCRIPTION

Narrows Complex

Begin at a point about 800 feet north of Narrows Dam and 400 feet west of the Yadkin River; then south following the course of Yadkin River about 800 yards to the intersection with the Pine Street extension road; then east across Yadkin River to a point about 200 feet east of the river on the Montgomery County side; then north about 675 yards to a point about 400 feet east of Yadkin River; then west across Yadkin River to the beginning.

Badin Historic District

Begin at the intersection of Falls Road and N.C. 740; then southwest along N.C. 740 to Ballpark Street; then south along Ballpark Street to the north boundary of the Stanly County Country Club property; then follow north boundary of the Stanly County Country Club east for about 875 yards to the intersection with Golf Course Road; continue east across the Stanly County Country Club property for about 500 feet to the southern boundary of the Stanly County Country Club; follow southern boundary of the Stanly County Country Club north by northeast for about 400 yards until the intersection with the south property line of Falls Road; continue northeast along Stanly Street until the intersection with Pine Street; then west along Pine Street to intersection with Spruce Street; then north to property line on north side of Pine Street; then west to intersection with Field Lane; then north on Field Lane to property line on north side of Walnut Street; then west to property line on north side of Falls Road; then west to N.C. 740; then south to the beginning.


West Badin Historic District


Begin at the intersection of Wood and Lee streets; then northwest along Wood Street to the intersection with Grant Street; then southwest to Sims Street; then northwest to Jackson Street; then northeast to west property line of Sherman Street; then northwest along property line to north property line of Lincoln Street; then northeast to Thomas Street; then southeast to Roosevelt Street; then northeast on Roosevelt Street to Stuart Street; continue northeast on Stuart Street to east property line of Marion Street; then south along property line to south property line of Sumpter Street; then west along property line to Roosevelt Street; then south along Roosevelt Street to intersection with Lee Street; then southwest to the beginning.

Badin Multiple Resource  
 West Badin Historic District  
 Badin and New London Quadrangles  
 Zone 17 Scale 1:24000  
 Badin Quadrangle  
 A 17 579780/3919200  
 B 17 579840/3918380  
 New London Quadrangle  
 C 17 579420/3918050  
 D 17 579050/3918640  
 E 17 579440/3919080

Badin Multiple Resource  
 Narrows Complex  
 Badin Quadrangle  
 Zone 17 Scale 1:24000  
 A 17 581940/3919780  
 B 17 582520/3920030  
 C 17 582740/3919430  
 D 17 582420/3919240

Badin Multiple Resource  
 Badin Historic District  
 Badin Quadrangle  
 Zone 17 Scale 1:24000  
 A 17 580220/3918330  
 B 17 581470/3918440  
 C 17 580840/3917500  
 D 17 580400/3917460  
 E 17 579780/3917800





LAGOON

5

12 13 14 15 16 17 18 19 20 21  
22 23 24 25 26 27 28 29 30 31

32 33 34 35 36 37 38 39 40 41 42 43 44 45

HENDERSON ST.

BOYDEN

STANLY COUNTY CLUB PROPERTY LINES

Badin Historic District

166

167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000

West Badin Historic District



Narrows Complex

